



18060 Modular Adj. Tee Assembly Aluminum Magnesium 1-1/2" IPS (1.94" ID)



NOTE: DIMENSIONS LOCATED IN REDS ARE COMMON
SEE EACH DIMENSION FOR EACH FITTING



#17S Modular Adjustable Tee Assembly

SCALE: 1/4"=1"

PIPE SIZE F'	ENGLISH UNITS (INCHES)						PIPE SIZE F'	METRIC UNITS (MM)							
	A	B	G	D	E	F		G	A	B	G	D	E	F	G
1 1/2"	1.30	2.0	2.5	1.0	1.75	2.75		33	51	64	25	44	44	70	70
1"															
3/4"															

[Click here for chart](#)

BUYRAILINGS
ARCHITECTURAL AND INDUSTRIAL RAILINGS

2" IPS
Schedule 40 2.387" O.D., 0.154" Wall
Schedule 80 2.387" O.D., 0.218" Wall

1 1/2" IPS
Schedule 40 1.915" O.D., 0.140" Wall
Schedule 80 1.915" O.D., 0.200" Wall

1" IPS
Schedule 40 1.315" O.D., 0.140" Wall
Schedule 80 1.315" O.D., 0.181" Wall

3/4" IPS
Schedule 40 0.940" O.D., 0.110" Wall
Schedule 80 0.940" O.D., 0.154" Wall

1/2" IPS
Schedule 40 0.625" O.D., 0.100" Wall
Schedule 80 0.625" O.D., 0.134" Wall