



18060 Modular Adj. Tee Assembly Aluminum Magnesium 1-1/2" IPS (1.94" ID)



NOTE: DIMENSIONS LOCATED IN BOWTS ARE COMMON
SEE EACH DIMENSION FOR EACH FITTING



#17S Modular Adjustable Tee Assembly

SCALE: 1/4"=1"

PIPE SIZE	ENGLISH UNITS (INCHES)						PIPE SIZE	METRIC UNITS (MM)							
	A	B	G	D	E	F		G	A	B	G	D	E	F	G
1/2"	1.30	2.0	2.5	1.0	1.75	2.75	1/2"	33	51	64	25	45	44	70	70
3/4"	1.50	2.25	2.75	1.25	2.0	3.0	3/4"	38	57	70	32	51	51	76	76
1"	1.75	2.5	3.0	1.5	2.25	3.5	1"	44	64	76	38	57	57	89	89
1 1/2"	2.25	3.25	3.75	2.0	2.75	4.5	1 1/2"	57	83	95	51	70	70	114	114

[Click here for chart](#)

BUYRAILINGS
ARCHITECTURAL AND INDUSTRIAL RAILINGS

2" IPS
Schedule 40 2.387" O.D., 0.154" Wall
Schedule 80 2.387" O.D., 0.218" Wall

1 1/2" IPS
Schedule 40 1.912" O.D., 0.140" Wall
Schedule 80 1.912" O.D., 0.200" Wall

1" IPS
Schedule 40 1.315" O.D., 0.140" Wall
Schedule 80 1.315" O.D., 0.191" Wall

3/4" IPS
Schedule 40 0.950" O.D., 0.133" Wall
Schedule 80 0.950" O.D., 0.177" Wall

1/2" IPS
Schedule 40 0.625" O.D., 0.133" Wall
Schedule 80 0.625" O.D., 0.154" Wall